

## Compressor Station

### ETC Tiger Pipeline/Shreveport, LA

Scope of work included site development of approximately 20 acres consisting of excavation, grading, sub-grade stabilization and installation of parking lot and rock roads. Over 400 drilled piers of various sizes were installed utilizing the slurry method and 2700 CY of structural concrete was poured for equipment foundations.

Despite extreme summer temperatures and additions to the scope of work increasing the project value by over 50%, the project was completed within the original time frame.

