

Terminal Expansion

Magellan/Houston, TX

The scope of this project includes site preparation, site drainage, detention pond, installation of three (3) truck bays with by-pass lane (2007) and expansion of three (3) additional bays (2009), installation of four (4) elevated MCC buildings, installation of approximately 10,000(+) CY's of concrete for truck road as well as twenty five (25) tank rings (2007-2017) with three (3) more scheduled for completion in 2017, thirty plus (30+) deep well vertical can pump foundations, miscellaneous pump foundations and piers including sphere and bullet tank foundations, installation of six (6) sumps and platforms, installation of structural steel for miscellaneous equipment foundations and walkways, installation of approximately 4,000 LF of road work and

approximately 10,000 LF of dike wall, installation and modification of tank farm containment dikes and grading, installation of crude manifold and manifold expansion (2012-2015), installation of pipe, cable tray rack and truck loading scales and installation of underground HDPE piping for fire suppression system.

